



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites: <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

No: MGPGIDS/EC/AE/F-302/2023-24/ 589

Dated: 17/11/23

SHORT QUOTATION NOTICE

On behalf of the Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry sealed Quotations are invited from the Registered Contractors in PWD, CPWD, Class-V and above for the work of "Additional provisions and alternate flooring inside P.G. clinic of Periodontics Dept.. Third floor, Dental Dept. Block-III in MGPGIDS." (Contractors are requested to visit the site before quote in the rates and acknowledgement to be submitted with "declaration about site inspection" in the form available in MGPGIDS Website along with schedule).

The **Schedule** of items are available in this Institution website <https://mgpgi.py.gov.in> which may downloaded and your rates quoted accompanying the schedule stated above.

The sealed quotation superscribed as "Additional provisions and alternate flooring inside P.G. clinic of Periodontics Dept.. Third floor, Dental Dept. Block-III in MGPGIDS" will be received by / addressed to Assistant Engineer, Administrative Block (F.F), MGPGIDS, Gorimedu, Puducherry on all working days up to **3.30 PM on or before 27.11.2023 and opened on same day at 4.00 PM.**

All the Quotations should be accompanied by **Earnest Money Deposit (EMD) @2% from your quoted value in the form of Demand Draft / Pay Order drawn in favour of the Dean, Mahatma Gandhi Post Graduate Institute of Dental Sciences, Gorimedu, Puducherry.** The quotation without EMD will be summarily rejected.

If the opening day of the quotation happens to be a public holiday the same will be received and opened on the next working day at the same time.

The work should be carried out as per the CPWD Manual & Specifications and instruction of Engineer in-charge, and completed within **one Month**, failing which MGPGIDS reserves the right to recover compensation for delay at the rate of 1% of the quoted amount pending subject to a maximum of 10% of the quoted amount.

The undersigned reserves the right to accept or reject whole or any part of the quotation and the quotationer shall be bound to perform the same at the rate quoted by him.

Note:

This quotation notice along with "Schedule 2 (two) pages and Site Inspection Form towards acknowledgement" are available in this Institution Website <https://mgpgi.py.gov.in> which may be downloaded.


ASSISTANT ENGINEER

Encl.: Schedule containing pages 1, 2 & Site Inspection Form.

✓ Copy to the Programmer, MGPGIDS for uploading on MGPGIDS Website along with the encloser stated above please.



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites: https://mgpgi.py.gov.in
https://mgpgi.edu.in

Name of Work: - Additional provisions and alternate flooring inside P.G. clinic of Periodontics Dept.. Third floor, Dental Dept. Block-III in MGPGIDS.		Mahatma Gandhi post Graduate Institute of Dental Sciences Engineering cell, Gorimedu, Puducherry.			
Item No.	Description	Quantity	Rate	Unit	Amount
1	Code No. 11.41.2A Providing and laying fully vitrified floor tiles of size 600 x600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622 of approved make (Nitco / Rak / Johnson /Asian) in all colours and shades , laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) , including grouting the joints with white cement and matching pigments etc., complete - size of tile 600 x600 mm.	81.00		Sqm	
2	Code 11.42 Deduct for not using 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles	76.10		Sqm	
3	Code 11.43 Fixing glazed /ceramic / Vitrified floor tiles with cement based high polymer modified quick - set tile adhesive (water based) conforming to IS:15477, in average 3 mm thickness - (Using 5 kg adhesive per sqm of tile area).	76.10		Sqm	
4	Code 14.85 Taking out existing wooden door shutter, repair by cutting , painting etc.and refixing of repaired door shutters to existing door frames , including replacement of hinges with screws etc. as require all complete.	3.10		Sqm	
5	Code 9.23 Extra for providing lipping with teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	3.10		Sqm	
6	Code 9.24.1 Extra for providing vision panel not exceeding 0.1 sqm in all type of flush doors (cost of glass excluded) (overall area of door shutter to be measured) - Rectangular or square	3.10		Sqm	
7	17.31 Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6mm thick hard board ground fixed to wooden cleats with C.P.brass screws and washers complete .	1.00		each	
8	18.51.1 Providing and fixing C.P.brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms - 15 mm nominal bore.	2.00		each	
9	17.73.1 Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fitting arrangement of approved quality and colour - 450 mm long towel rail with total.	1.00		each	
10	Providing and fixing C.P.brass elbow operated bib cock of approved quality conforming to IS standards for hospitals - 15 mm nominal bore.	1.00		each	

ASSISTANT ENGINEER
MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN
PUDUCHERRY

-Contd. page. 2/2..

11	Making cut opening on existing half brick finished wall of size 85x47cm for servicing counter with a smooth finish of edge plastering, fixing of old cuddapha slab (issued by Dept.), aluminium sliding shutter with 4mm thick galss, rubber beading, wheel & chanel etc, complete. The rate include of all labou for cutting making walls, tools & plants, accessories, all materials, transportation etc. complete asper the direction of the engineer in charge.	1.00		No.	
12	Making cut opening on existing 23cm finished wall of size 50cm dia for exhaust fan provision at inside the sterlizer room with a smooth louver half rotating type anty caroded MS sttel etc, complete. The rate include of all labour for cutting making walls, tools & plants, accessories, all materials, etc. complete asper the direction of the engineer in charge.	1.00		No.	
13	Making cut opening on existing 23cm finished wall of size 90x90cm for window provision at inside the sterlizer room with a louver type aluminium frame, 4mm thick glass and aluminium beading, half rotating aluminium type hinges etc. complete. The rate include of all labour for cutting making walls, tools & plants, accessories, all materials, etc. complete asper the direction of the engineer in charge.	1.00		Job	
14	Construction of platform structure at inside sterlizer room of size 535cmx60cmx85cm with a finish of half brick supporting wall of size 55cmx85cm @ 7nos., base raised @ 10cm thick with brick on edging, brick agregate cement concre mix 1:5:10 (one cement 5 coarse sand 10 brick agrigate 25mm thick) over existing floor, top of platform finished with RCC precast slab @ 50mm thick & single side polished block colour cuddapha slab 20mm thick and midle part shef provision with block colour, cement plaster with a mix of 1:4 (one cement, four fine sand) to all exposed brick walls, base platfor, slab joints, patches smooth finishes etc. complete.	1.00		Job	
15	Removing old sink and re-fixing with suitable S.S (304 grade) square solid bare clap (2 nos. per sink), screws, holdfast, fixing on wall, placing in position, repolishing etc. comple asper direction of Engineer in charge.	2.00		Set	
16	Supplying and fixing of fabricated SS sink of size 600x450mm glading 2mm thick sheet (304 grade) & 300mm hight with suitable wall mount clamp provision, coach screws, holdfast, fixing in position etc. complete as per direction of engineer in charge.	1.00		No.	
17	Providing water supply & drainage system pipe lines & fixture at sinks inside sterlizer room. The rate includes all labour, materials, tools & platns, accessories etc. complete as per direction of engineer in charge.	1.00		Job	
18	Dismantling tile work in skirting laid in cement mortar including disposal of unserviceable material and base plastering of 20mm thick for skirting using cement mortar 1:4 (one sand: four fine sand) upto a length of 35 mtrs. - for thickness of tiles above 25 mm and upto 40 mm.	1.00		Job	
Total Amount in Rs					


ASSISTANT ENGINEER
 MAHATMA GANDHI
 POSTGRADUATE INSTITUTE OF DENTAL SCIENCE
 GOVT. OF PUDUCHERRY INSTN
 PUDUCHERRY

DECLARATION ABOUT SITE INSPECTION

To

The Assistant Engineer,
Engineering Cell, MGPGIDS,
Gorimedu,
Puducherry-6

Ref: Short Quotation Notice .No: MGPGIDS/EC/AE/F-302/2023-24/ dated

Sub: Site inspection

Name of the work : Additional provisions and alternate flooring inside P.G. clinic of Periodontics
Dept.. Third floor, Dental Dept. Block-III in MGPGIDS, Gorimedu, Puducherry.

Dear Sir,

It is hereby declared that, I / We the bidder inspected and examined the subject site and its surrounding and satisfy myself / ourselves as to the nature of the ground and sub-soil (so far as is practicable), the forms and nature of the site, the means of access to the site, the accommodation which may require and all necessary information as to risks, contingencies and other circumstances which may influence or affect our bid have been obtained. I / We the bidder shall have full knowledge of the site and no extra charge consequent upon any misunderstanding or otherwise shall be claimed in later date. I / We bidder shall be responsible for arranging and maintaining at own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a bid by me / us implies that I / We have read this notice and all other contract documents and has made myself /ourselves aware of the scope and specifications of the work to be done and local conditions and other factors having a bearing on the execution of the work.

Yours faithfully
(Duly authorized signatory of the bidder)