



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites: <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

No: MGPGIDS/EC/AE/F-180/2023-24/ 712

Dated: 22-12-2023

SHORT QUOTATION NOTICE

(2nd call)

On behalf of the Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry sealed Quotations are invited from the Registered Contractors in PWD, CPWD, Class-V and above for the work of "Additional provision and alternate flooring inside plaster room of Orthodontics Dept., first floor in MGPGIDS.." (Contractors are requested to visit the site before quoting in the rates and acknowledgement to be submitted with "declaration about site inspection" in the form available in MGPGIDS Website along with schedule).

The **Schedule** of items are available in this Institution website <https://mgpgi.py.gov.in> which may downloaded and your rates quoted accompanying the schedule stated above.

The sealed quotation superscribed as "Additional provision and alternate flooring inside plaster room of Orthodontics Dept., first floor in MGPGIDS." will be received by / addressed to Assistant Engineer, Administrative Block (F.F), MGPGIDS, Gorimedu, Puducherry on all working days up to **3.30 PM on or before 03.01.2024 and opened on same day at 4.00 PM.**

All the Quotations should be accompanied by **Earnest Money Deposit (EMD) @ 2% from your quoted value in the form of Demand Draft / Pay Order drawn in favour of the Dean**, Mahatma Gandhi Post Graduate Institute of Dental Sciences, Gorimedu, Puducherry. The quotation without EMD will be summarily rejected.


If the opening day of the quotation happens to be a public holiday the same will be received and opened on the next working day at the same time.

The work should be carried out as per the CPWD Manual & Specifications and instruction of Engineer in-charge, and completed within **45 days**, failing which MGPGIDS reserves the right to recover compensation for delay at the rate of 1% of the quoted amount pending subject to a maximum of 10% of the quoted amount.

The undersigned reserves the right to accept or reject whole or any part of the quotation and the quotationer shall be bound to perform the same at the rate quoted by him.

Note:

This quotation notice along with "Schedule" containing 2 (two) pages only and Site Inspection Form towards acknowledgement" are available in this Institution Website <https://mgpgi.py.gov.in> which may be downloaded.


ASSISTANT ENGINEER

Encl.: Schedule containing 2 (two) pages only & Site Inspection Form.

✓ Copy to Programmer, MGPGIDS for uploading on MGPGIDS Website along with schedule etc. are enclosed please.



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites: https://mgpgi.py.gov.in
https://mgpgi.edu.in

Name of Work: - Additional provision and alternate flooring inside plaster room of Orthodontics Dept., first floor in MGPGIDS			Mahathma Gandhi post Graduate Institute of Dental Sciences Engineering cell, Gorimedu, Puducherry.		
Item No.	Description	Quantity	Rate	Unit	Amount
1	Code No. 11.41.2A Providing and laying fully vitrified floor tiles of size 600 x600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622 of approved make (Nitco / Rak / Johnson /Asian) in all colours and shades , laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) , including grouting the joints with white cement and matching pigments etc., complete - size of tile 600 x600 mm.	21.00		sqm	
2	Code 11.42 Deduct for not using 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles	-21.00		sqm	
3	Code 11.43 Fixing glazed /ceramic / Vitrified floor tiles with cement based high polymer modified quick - set tile adhesive (water based) conforming to IS:15477, in average 3 mm thickness - (Using 5 kg adhesive per sqm of tile area).	21.00		sqm	
4	Code 14.85 Taking out existing wooden door shutter, repair by cutting , painting etc.and refixing of repaired door shutters to existing door frames , including replacement of hinges with screws etc. as require all complete.	2.10		sqm	
5	Code 9.23 Extra for providing lipping with teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).	2.10		sqm	
6	18.51.1 Providing and fixing C.P.brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms - 15 mm nominal bore.	2.00		each	
7	Construction of platform structure at inside plaster room with a finish of half brick supporting wall of size 55cmx85cm approx. 7nos., base raised @ 10cm thick with brick on edging, brick aggregate cement concrete mix 1:5:10 (one cement 5 coarse sand 10 brick aggregate 25mm thick) over existing floor, top of platform finished with RCC precast slab @ 50mm thick & single side polished block colour granite stone slab 20mm thick and middle part shelf provision with block colour kadapa slab, cement plaster with a mix of 1:4 (one cement, four fine sand) to all exposed brick walls, base platform, slab joints & patch finishes etc. complete.	7.00		metre	
8	Code No.: 8.5 Extra for providing opening of required size & shape for wash basin / kitchen sink in kitchen platform , vanity counter and similar location in marble / granite / stone work , including necessary holes for pillar taps etc . Including moulding ,rubbing and polishing of cut edges etc.complete.	1.00		each	


ASSISTANT ENGINEER
MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.

9	Providing water supply & drainage system; pipe lines & fixture at sinks inside plaster room by connecting existing water supply & drainage system. The rate includes all labour, materials, tools & platns, accessories etc. complete as per direction of engineer in charge.	1.00		job	
10	Dismantling tile work in skirting laid in cement mortar including disposal of unserviceable material and base plastering of 20mm thick for skirting using cement mortar 1:4 (one sand: four fine sand) upto a length of among 35 mtrs. - for thickness of tiles above 25 mm and upto 40 mm (inside the plaster room skirting).	1.00		job	
11	Electrification inside plaster room with required 15A / 5A plug points and switches by making on walls concealed / open pattern. The rate includes all labour, materials, wires,, pipes, bends, all fixtures etc. complete as per the direction of Engineer incharge.	1.00		job	
Total Amount in Rs					


ASSISTANT ENGINEER
 MAHATMA GANDHI
 POST GRADUATE INSTITUTE OF DENTAL SCIENCE
 GOVT. OF PUDUCHERRY INSTN
 PUDUCHERRY