



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites: <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

No. MGPGI/EC/AE/F-294/2023-24/ 433

Dated: 13-9-2023

SHORT QUOTATION NOTICE

On behalf of the Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry sealed Quotations are invited for the work of "Repairing works at false ceiling inside Dr. R. Radhakrishnan Hall (Seminar Hall-B), third floor, DD Block in MGPGIDS" from the eligible Firm / Registered Contractors in PWD, CPWD which the items tentatively given below:

Item No.	Description of Items	Qty	Rate in Rs	Unit	Amount in Rs
1	Providing and fixing of pin type mineral false ceiling tiles pattern of size 600x600mm in existing aluminium / metal frame structure of false ceiling make of Gyptech, USG or equivalent by providing necessary screws, rivets, pivets & accessories etc. as required while placing false ceiling tile. The rate includes all labour, materials, specials, transportation, machineries, tools & plants etc. complete asper the direction of the engineer-in-charge.	158		sqm	
2	Labour charges for fixing of old pin type mineral false ceiling tiles pattern of size 600x600mm in existing aluminium / metal frame structure of false ceiling by providing necessary screws, rivets, pivets, adjustment to existing chanel & accessories etc. as required while placing tile. The rate includes all labour, tools & plants etc. complete asper the direction of the engineer-in-charge.	54		Sqm	
3	Providing and fixing of mineral gypsum board false ceiling on vertical surface in existing aluminium / metal frame structure of false ceiling by providing necessary screws, rivets, pivets, jointing, pasting, painting finishes & suitable accessories etc.. The rate includes all labour, materials, specials, transportation, machineries, tools & plants etc. complete asper the direction of the engineer-in-charge.	61		sqm	
4	Code No. 12.71 Providing and fixing 1/2"tk Daikin mineral false ceiling tiles prima fine fissued regular edge or equivalent having fire propogation test of 'class O' as per B.S.476 part 6, with a flame spread of class A of US federal spec. SS/S/118B . Thermal conductivity at 0.045K cal/mhc of JIS A 1412. Noice reduction co-efficient (NRC) of 0.55-0.6of ASTM C 423,light reflectance of LR 1(>75% os ASTM C 523) CAC at 36 of ASTM E 413 and asbestos free and humidity resistance of RH 99% of size 600 x 600 mm with interlocking metal grid of hot dipped galvanized steel sections (galvanized at 170 gm / sqm) with pre-finished in baked polyester paint , consisting of main runners of size 24x33 mm T-sections made of 0.27mm thick (minimum) sheet spaced at 1200 mm centre to centre and secondary T hot dipped galvanized steel section of size 28x24 mm made of 0.27 mm tk (minimum) sheet with pre finished in baked polyester paint to be interlocked in between main runner at 600 mm centre to centre to form overall grid of 600x600 mm laying 15 mm thick mineral fibre false ceiling tiles in the grid suspended by hanger rods 60 cm long with bolts @ 1.2 m c/c including cutting /making openings of services like fittings , diffusers, grills, smoke detectors, etc including providing necessary wall angle of size 19 x 19 x 0.45 mm on all four sides including scaffolding etc., complete- ceiling upto 6.5 m heights.	55		sqm	
					-P.T.O

5	Alteration to existing aluminium / metal false ceiling structure by cutting making as suitable for providing proposed tiled pattern false ceiling structure . The rate include of all labour, suitable accessories, tools & plants etc. complete as per the direction of the engineer in-charge.	55		sqm	
6	Supplying and fixing of welded steel wire fabric of required width rectangular mesh painted with two or more coats of enamel paint of approved shade over a coat of primer.	4		Sqm	

Sealed quotations are invited from the Registered Contractors of PWD / CPWD, Class V and above superscribed as **“Repairing works at false ceiling inside Dr. R. Radhakrishnan Hall (Seminar Hall-B), third floor, DD Block in MGPGIDS”**. The quotation will received by the Assistant Engineer, Administrative Block (First Floor), MGPGIDS, Indira Nagar, Gorimedu, Puducherry on all working days up to 3.30 PM on 20.9.2023 and opened on the same day at 4.00 PM.

If the opening day of the quotation happens to be a public holiday the same will be received and opened on the next working day at the same time.

All the Quotations should be accompanied by **Earnest Money Deposit (EMD) for an amount of Rs.5313/- in the form of Demand Draft / Pay Order drawn in favour of the Dean, Mahatma Gandhi Post Graduate Institute of Dental Sciences, Gorimedu, Puducherry**. The quotation without EMD will be summarily rejected.

The work should be carried out as per the CPWD Manual & Specifications and instruction of Engineer in-charge, and completed within one Month, failing which MGPGIDS reserves the right to recover compensation for delay at the rate of 1% of the quoted amount pending subject to a maximum of 10% of the quoted amount.

The undersigned reserves the right to accept or reject whole or any part of the quotation and the quotationer shall be bound to perform the same at the rate quoted by him.

Note:

This quotation notice is available in this Institution Website <https://mgpgi.py.gov.in> which may be downloaded.

ASSISTANT ENGINEER

✓ Copy to Programmer, MGPGIDS for uploading on MGPGIDS Website please.