



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites: <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

No: MGPGIDS/EC/AE/F-315/2024-25/ 904

Dated: 23 SEP 2024

SHORT QUOTATION NOTICE

On behalf of the Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry sealed Quotations are invited from the Registered Contractors in PWD, CPWD, Class-V and above for the work of "Arresting leakages by attending repairing works to closets & lines with replacement of flooring at toilets for 1st year Students, Third floor, Dental Dept. Block-I in MGPGIDS." (Contractors are requested to visit the site before quoting in the rates and acknowledgement to be submitted with "declaration about site inspection" in the form available in MGPGIDS Website along with schedule).

The **Schedule** of items are available in this Institution website <https://mgpgi.py.gov.in> which may downloaded and your rates quoted accompanying the schedule stated above.

The sealed quotation superscribed as "Arresting leakages by attending repairing works to closets & lines with replacement of flooring at toilets for 1st year Students, Third floor, Dental Dept. Block-I in MGPGIDS" will be received by / addressed to Assistant Engineer, Administrative Block (F.F), MGPGIDS, Gorimedu, Puducherry on all working days up to **3.30 PM on or before 30.09.2024 and opened on same day at 4.00 PM.**

All the Quotations should be accompanied by **Earnest Money Deposit (EMD) ₹ 1,751/- in the form of Demand Draft / Pay Order drawn in favour of the Dean, Mahatma Gandhi Post Graduate Institute of Dental Sciences, Gorimedu, Puducherry.** The quotation without EMD will be summarily rejected.

If the opening day of the quotation happens to be a public holiday the same will be received and opened on the next working day at the same time.

The work should be carried out as per the CPWD Manual & Specifications and instruction of Engineer in-charge, and completed within **1 (one) Month**, failing which MGPGIDS reserves the right to recover compensation for delay at the rate of 1% of the quoted amount pending subject to a maximum of 10% of the quoted amount.

The undersigned reserves the right to accept or reject whole or any part of the quotation and the quotationer shall be bound to perform the same at the rate quoted by him.

Note:

This quotation notice along with "Schedule" containing 3 (three) pages only and Site Inspection Form towards acknowledgement" are available in this Institution Website <https://mgpgi.py.gov.in> which may be downloaded.


ASSISTANT ENGINEER

Encl.: Schedule containing 3 (three) pages only & Site Inspection Form.



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in.
mgpgids@gmail.com
Websites: <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

Name of Work: - Arresting leakages by attending repairing works to closets & lines with replaceemnt of flooring at toilets for 1st year Students, Third floor, Dental Dept. Block-I in MGPGIDS.			Mahathma Gandhi post Graduate Institute of Dental Sciences Engineering cell, Gorimedu, Puducherry.		
Item No.	Description	Quantity	Rate	Unit	Amount
1	Code No.11.40: Providing and laying rectified glazed ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer) of 1st quality conforming to IS:15622 of approved make (Somany / Nitco / Jhonson) in all colours , shades, except white, ivory, grey, fume red brown, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigments etc., complete.	25.00		sqm	
2	Code No.11.42: Deduct for not using 20 mm thick cement mortar 1:4 (1 cement : 4coarse sand) bedding in laying of floor tiles and jointing with grey cementslurry @ 3.3 kg/ sqm.	-19.00		sqm	
3	Code No.11.43: Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymermodified quick-set tile adhesive (Water based) conforming to IS: 15477,in average 3mm thickness.	20		sqm	
4	Code No. 14.80.2 Providing & fixing white vitreous china water closet squatting pan (Indian type) along with "S" or "P" trap including dismantling of old WC seat and "S" or "P" trap at site complete with all operations including all necessary materials, labour and disposal of dismantled material i/c malba , all complete - Orissa pattern W.C.Pan of size 580x440 mm.	2		no.	
5	Code No.17.2.1 Providing and fixing white vitreous china pedestal type water closet (European type W.C.pan) with seat and lid, 10 litre low level white P.V.C. flusing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231,with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required - W.C. pan with ISI marked white solid plastic seat and lid.	1		each	
6	Code No. 15.52 Dismantling of flushing cistern of all types (C.I / PVC / Vitrous china) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead	9		each	
7	Code No.17.7.1 Providing and fixing wash basin with C.I. brackets, 15mm C.P. brass pillar taps ,32 mm C.P.brass waste of standard pattern , including painting of fittings and brackets ,cutting and making good the walls wherever required - white Vitreous China wash basin size 630x450 mm with a pair of 15 mm C.P.brass pillar taps	3		each	

8	Code No. 25.1 Raking out joints of stone masonry surface to the required width and depth , with due care and precaution, by mechanical / manual means, including preparing and cleaning the surface for re- pointing / refilling of joints , including disposal of rubbish to the dumping ground within 50 metre lead	25		sqm	
9	Code No. 2.1.1A Earth work in surface excavation not exceeding 30cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including getting out and disposal of excavated earth up to 50m and lift up to 1.5m - All kinds of soil	3.05		cum	
10	Code No. 14.85 Taking out existing wooden door shutter , repair by cutting , painting etc.and refixing of repaired door shutters to existing door frames , including replacement of hinges with screws etc. as require all complete.	8		Sqm	
11	Code No.17.32.2 Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6mm thick hard board backing - rectangular shape 453 x 357 mm.	3		each	
12	Code No.18.53.1 Providing and fixing C.P.brass angle valve for basin mixer and geyser points of approved quality conforming to IS: 8931- 15 mm nominal bore.	8		each	
13	Code No.18.56.1 Providing and fixing PTMT pillar cock of approved quality and colour - 15 mm nominal bore , 107 mm long, weighing not less than 110 gms	3		each	
14	Code No. 18.21.1.2 Providing and fixing unplasticised PVC connection pipe with brass unions - 30 cm length - 20 mm nominal bore	8		each	
15	Code No.16.100 Acid cleaning for the existing Mosaic floors , glazed tiles work and removing the stains and decays to give a glassy look etc complte (The Acid used shall be 32% concentrated hydrochloric acid after taking on the precautionary measures)	93		sqm	
16	Code No. 18.9.11 Providing and fixing ASTM pipes including all ASTM plain& brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing . This includes jointing of pipes & fitting with one step ASTM solvent cement and testing of joints complete (Internal work exposed on wall) - 20mm nominal outer dia pipes	14		metre	
17	Code No.18.76.1 Cutting holes upto 30x30 cm in walls including making good the same with common burnt clay F.P.S.(non - modular) brick	3		each	
18	Code No.19.33.2 Providing and fixing on wall / column face unplasticised - PVC soil and waste pipes (type B) conforming to IS :13592 - 1992 including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion - Single socketed pipes 75mm diameter	4.2		metre	
19	Code No.19.33.2A Providing and fixing on wall / column face unplasticisd - PVC moulded fittings / accessories for unplasticisd - PVC soil and waste pipes conforming to IS :14735 -1999 including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion - Single tee with door - 75x75x75mm	1		each	
20	Code No.19.33.2B Providing and fixing on wall / column face unplasticisd - PVC moulded fittings / accessories for unplasticisd - PVC soil and waste pipes conforming to IS :14735 -1999 including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion -Single tee without door - 75x75x75mm	4		each	

21	Code No.19.33.2C Providing and fixing on wall / column face unplasticisd - PVC moulded fittings / accessories for unplasticisd - PVC soil and waste pipes conforming to IS :14735 -1999 including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion - Bend 75 mm.	2		each	
22	Code No. 19.33.1 Providing and fixing on wall / column face unplasticed - PVC soil and waste pipes (type - B) conforming to IS : 13592- 1992 including jointing with seal ring conformation to IS : 5382 leaving 10mm gap for thermal expansion - single socked pipes -110mm diametre	1.5		metre	
23	Code No. 19.33.1B Providing and fixing on wall face / column face unplasticised - PVC moulded fittings / accessories for unplasticisd - PVC soil and waste pipes conforming to IS : 14735 -1999 including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion - Single tee without door - 110 x110x110 mm	1		each	
24	Code No. 19.33.1C Providing and fixing on wall face / column face unplasticised - PVC moulded fittings / accessories for unplasticisd - PVC soil and waste pipes conforming to IS : 14735 -1999 including jointing with seal ring conforming to IS : 5382 leaving 10mm gap for thermal expansion - bend 110mm	2		each	
25	Code No. 17.60.2.2 Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors - 100mm inlet and 75mm outlet - sand cast iron S&S as per IS: 1729	1		each	
26	Code No. 31.167.1J Providing and fixing in position UPVC moulded reducer coupler (Finolex / jain)(0.6 Mpa) conforming to IS 7834 part II and ISI marked,including labour charges for jointing, jointing materials etc,complete - 110 x 75mm dia	1		no.	
27	Code No. 15.44.1 Dismantling G.I.pipes (external work) including excavation and refilling trenches after taking out the pipes, manually / by mechanical means including stacking of pipes within 50 metres lead- 15mm to 40mm nominal bore	15		metre	
28	Code No. 17.28.1.1 Providing and fixing P.V.C. waste pipe for sink or wash basin including PVC waste fittings complete - semi rigid pipe - 32mm dia	3		each	
29	Code No. 4.1.10A Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 12.5mm nominal size)	0.6		cum	
Total Amount in Rs					-





**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.co
Websites: <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

DECLARATION ABOUT SITE INSPECTION

To

:
The Assistant Engineer,
Engineering Cell, MGPGIDS,
Gorimedu,
Puducherry-6

Ref: Short Quotation Notice .No: MGPGIDS/EC/AE/F-315/2024-25/ dt. 23.09.2024.

Sub: Site inspection

Name of the work : Arresting leakages by attending repairing works to closets & lines with replacement of flooring at toilets for 1st year Students, Third floor, Dental Dept. Block-I in MGPGIDS

Dear Sir,

It is hereby declared that, I / We the bidder inspected and examined the subject site and its surrounding and satisfy myself / ourselves as to the nature of the ground and sub-soil (so far as is practicable), the forms and nature of the site, the means of access to the site, the accommodation which may require and all necessary information as to risks, contingencies and other circumstances which may influence or affect our bid have been obtained. I / We the bidder shall have full knowledge of the site and no extra charge consequent upon any misunderstanding or otherwise shall be claimed in later date. I / We bidder shall be responsible for arranging and maintaining at own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a bid by me / us implies that I / We have read this notice and all other contract documents and has made myself /ourselves aware of the scope and specifications of the work to be done and local conditions and other factors having a bearing on the execution of the work.

Yours faithfully
(Duly authorized signatory of the bidder).