



MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites: <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

No: MGPGIDS/EC/AE/F-296/2023-24/ 366

Dated: 21-8-2023

SHORT QUOTATION NOTICE

(2nd Call)

On behalf of the Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry sealed Quotations are invited from the Registered Contractors in PWD, CPWD, Class-V and above for the work of "Re-construction of damaged Compound wall in Main road southern boundary / opp. to AD Block of MGPGIDS Campus, Gorimedu, Puducherry."

The **Schedule** of items is available in this Institution website <https://mgpgi.py.gov.in> which may downloaded and submit your rates accompanying the schedule stated above.

The sealed quotation superscribed as "Re-construction of damaged Compound wall in Main road southern boundary / opp. to AD Block of MGPGIDS Campus, Gorimedu, Puducherry" will be received by / addressed to Assistant Engineer, Administrative Block (F.F), MGPGIDS, Gorimedu, Puducherry on all working days up to **3.30 PM on or before 28.08.2023 and opened on same day at 4.00 PM.**

The successful bidder has to remit the Earnest Money Deposit at 2% of the quoted value in the form of Demand Draft / Pay Order drawn in favour of The Dean, Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry-6.

If the opening day of the quotation happens to be a public holiday the same will be received and opened on the next working day at the same time.

The work should be carried out as per the CPWD Manual & Specifications and instruction of Engineer in-charge, and completed **within one Month**, failing which MGPGIDS reserves the right to recover compensation for delay at the rate of 1% of the quoted amount pending subject to a maximum of 10% of the quoted amount.

The undersigned reserves the right to accept or reject whole or any part of the quotation and the quotationer shall be bound to perform the same at the rate quoted by him.

Note:

This quotation notice & Schedule is available in this Institution Website <https://mgpgi.py.gov.in> which may be downloaded.


ASSISTANT ENGINEER

Encl.: Schedule containing pages 1 & 2 only.



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
Fax : 0413-2278124 / 2277255
Gram : 'PONDENT'
E-mail : mgpgids@bsnl.in
mgpgids@gmail.com
mgdch.pon@nic.in

SCHEDULE

Name of Work: - Re-construction of damaged Compound wall in Main road southern boundary / opp. to AD Block of MGPGIDS Campus, Gorimedu, Puducherry.		Mahathma Gandhi post Graduate Institute of Dental Sciences Engineering cell, Gorimedu, Puducherry.			
S.No	Description	Qty.	Rate (Word & figre)	Unit	Amount in Rs
1	Code No. 15.7.4:- Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - in cement mortar.	4.60		Cum	
2	Code No. 2.6.1A:- Earthwork in excacavation over areas (exceeding 30 cm in depth , 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth lead upto 50m and lift upto 1.5m - disposed earth to be levelled and neatly dresses - all kinds of soil.	2.00		Cum	
3	Code No. 4.1.10:- Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	2.00		Cum	
4	Code No. 2.25:- Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and lift upto 1.5m.	2.50		Cum	
5	Code No.5.1.2 Providing and laying in position specified grade of reinforced cement concrete , excluding the cost of centering , shuttering , finishing and reinforcement - All work upto plinth level 1:1.5:3 (1cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	1.50		Cum	
					Cntd.2/2..


ASSISTANT ENGINEER
MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PUDUCHERRY
92
21-08-2023

MGPIDS-F296-Schedule Page 2/2..				
6	Code No.5.2.2 Reinforced cement concrete work in walls (any thickness) , including attached pilasters, buttresses , plinth and sting courses , fillets , columns , pillars , piers , abutments , posts and struts etc. upto floor five level excluding cost of centering , shuttering , finishing and reinforcement - 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size) .	2.50		Cum
7	Code 5.22.7 Steel reinforcement for R.C.C.work including straightening , cutting , bending , placing in position and binding all complete upto plinth level - Thermo -Mechanically treated bars (ISI BRAND OF APPROVED MAKE) Fe - 415 or more	58.00		kg
8	Code 5.22A.7 Steel reinforcement for R.C.C.work including straightening , cutting , bending , placing in position and binding all complete above plinth level - Thermo - Mechanically Treated bars (ISI BRAND OF APPROVED MAKE) Fe - 415 or more	173.00		kg
9	Code 13.1.1:- 5.9.1 Centering and shuttering including strutting , propping etc and removal of form for - foundations, footings, bases of columns etc for mass concrete	5.00		Sqm
10	Code 5.9.2 Centering and shuttering including strutting , propping etc and removal of form for - Walls (any thickness) including attached pilasters , butteresses , plinth and string courses etc.	33.00		Sqm
11	Code 13.1.1:- 12mm cement plaster of mix -1:4 (1 cement : 4 fine sand)	17.00		Sqm
12	Code 13.47.1 Finishing walls with premium acrylic smooth exterior paint with silicone additives of required shade - New work (two or more coats applied @1.43 ltr / 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg /10sqm)	17.00		Sqm
13	Code 13.50.3 Applying priming coat - with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron / steel works.	5.00		Sqm
14	Code 13.61.1 Painting with synthetic enamel paint of (sqm 86.78) approved brand and manufacutre to give an even shade - Two or more coats on new work	5.00		Sqm
Total Amount in Rs				


ASSISTANT ENGINEER
 MAHATMA GANDHI
 POSTGRADUATE INSTITUTE OF DENTAL SCIENCE
 GOVT. OF PUDUCHERRY INSTN
 PUDUCHERRY

21-08-2023