



MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006

Phone : 0413-2279601 - 2279606
Fax : 0413-2278124 / 2277255
Gram : 'PONDENT'
E-mail : mgpgids@benl.in
mgpgids@gmail.com
mgdch.pon@nic.in

No. MGPGI/EC/AE/F-289/2021-22/ 283

Dated 7 MAR 2022

SHORT QUOTATION NOTICE

(SECOND CALL)

On behalf of the Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry sealed Quotations are invited for the work of "Alternate utilization / Conversion for Campus Canteen and Stores in H.S Block Building, Ground floor in MGPGI" from the eligible Firm / Registered Contractors in PWD, CPWD and the items tentatively given below:

Item No.	Description of Items	Qty	Rate in Rs	Unit	Amount in Rs
1	Code No. 15.7.4:- Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - in cement mortar.	1.10		Cum	
2	Code No. 10.5.1:- Providing and fixing 1mm thick M.S.sheet door with frame of 40x40x6 mm angle iron and 3mm M.S.gusset plates at the junctions and corners , all necessary fittings complete, including applying a priming coat of approved steel primer - Using M.S.angels 40x40x6mm for diagonal braces	14.60		Sqm	
3	Code No.14.1.1:- Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq.metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead - with cement mortar 1:4 (1 cement : 4fine sand)	10.00		Sqm	
4	Code No. 14.17:- Raking out joints in lime or cement mortar and preparing the surface for repointing or replastering , including disposal of rubbish to the dumping ground within 50 metres lead.	10.00		Sqm	
5	Code No.6.1.1:- Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in - cement mortar 1:4 (1 cement : 4 coarse sand)	4.00		Cum	
6	Code No. 13.5.1:- 15mm cement plaster on rough side of single or half brick wall of mix - 1:4 (1 cement 4 coarse sand	28.00		Sqm	
7	Code No. 2.8.1:- Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50m - all kinds of soil.	2.60		Cum	
8	Code No. 2.25:- Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and lift upto 1.5m	3.50		Cum	
9	Code No. 4.1.10:- Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	3.50		Cum	
10	Code No. 13.47.1:- Finishing walls with premium acrylic smooth exterior paint with silicone additives of required shade - New work (two or more coats applied @1.43 ltr / 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg / 10sqm)	32.00		Sqm	Cntd.-2/3-

11	Code No. 14.43:- Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete exterior primer applied @ 2.20 kg / 10sqm)	100.00		Sqm	
12	Code No.14.45.1:- Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade - Old work (one or more coats)	432.00		Sqm	
13	Code No.10.6.2:- Supplying and fixing rolling shutters of approved make, made of required size M.S.laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to ISS :4454 -part 1 and M.S.top cover of required thickness for rolling shutters - 80 x 1.20mm M.S.laths with 1.25 mm thick top cover	2.50		Sqm	
14	Code 10.16.3:- Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete - electric resistance or induction butt welded tubes	100.00		Kg	
15	Code 13.48.3:- Painting steel work with deluxe multi surface paint to give an even shade. Two or more coat applied @ 0.90 ltr / 10 sqm over an under coat of primer applied @ 0.80 ltr / 10 sqm of approved brand and manufacture	47.00		Sqm	
16	Code 12.50:- Providing & fixing pre-coated galvanised iron profile sheets (size, shape, and pitch of corrugation as 0.50mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired. The sheet shall be fixed using self drilling / self tapping screws of size (5.5 x 55 mm) with EPDM seal, complete upto any pitch in horizontal / vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	35.00		Sqm	
17	Code 11.3.1:- Cement concrete flooring 1:2:4 (1 cement : 10 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete - 40mm thick with 20mm nominal size stone aggregate	27.00		Sqm	

Sealed quotations are invited from the Registered Contractors of PWD / CPWD, Class V and above superscribed as **"Alternate utilization / Conversion for Campus Canteen and Stores in H.S Block Building, Ground floor in MGPGI".** The quotation will be received by the **Assistant Engineer, Administrative Block (First Floor), MGPGI, Indira Nagar, Gorimedu, Puducherry - 6** on all working days up to 3.30 PM on 14.03.2022 and opened on the same day at 4.00 PM.

-page -3/3- (EC/MGPPI)-

All the Quotations should be accompanied by Earnest Money Deposit for an amount of Rs 3,353/- in the form of Demand Draft / Pay Order drawn in favour of the Dean, Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry-6. The quotation without EMD will be summarily rejected.

If the opening day of the quotation happens to be a public holiday the same will be received and opened on the next working day at the same time.

The work should be carried out as per the CPWD Manual & Specifications and Agreement formalities of PWD, Puducherry and the work should be completed **within Two Months** and as per the instruction of Engineer in charge, failing which MGPPI reserves the right to recover compensation for delay at the rate of 1% of the quoted amount pending subject to a maximum of 10% of the quoted amount. The undersigned reserves the right to accept or reject whole or any part of the quotation and the quotationer shall be bound to perform the same at the rate quoted by him.

Note: This quotation notice may also been downloaded from this Institution Website <https://mgpgi.py.gov.in>.


ASSISTANT ENGINEER

Copy to the Programmer, MGPPI for uploading on MGPPI Website please.