



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279602
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites : <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

No: MGPGIDS/EC/AE/F-288/2022-23/ 999

Dated: 20 JUN 2022
(3rd CALL)

SHORT QUOTATION NOTICE

On behalf of the Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry sealed Quotations are invited from the eligible Firm / Registered Contractors in PWD, CPWD, Class-V and above for the work of "Repair works inside the toilets of Medical and Surgery ward in MGPGIDS, Gorimedu, Puducherry".

The **Schedule** of items is available in this Institution website <https://mgpgi.py.gov.in> which may downloaded and submit your rates accompanying the schedule stated above.

The sealed **quotation superscribed as** "Repair works inside the toilets of Medical and Surgery ward in MGPGIDS, Gorimedu, Puducherry" will be received by / addressed to Assistant Engineer, Administrative Block (F.F), MGPGIDS, Gorimedu, Puducherry on all working days up to **3.30 PM on 27.06.2022** and opened on the same day at 4.00 PM.

All the **Quotations should be accompanied by Earnest Money Deposit (EMD) for an amount of Rs 3,053/- in the form of Demand Draft / Pay Order drawn in favour of the Dean, Mahatma Gandhi Post Graduate Institute of Dental Sciences, Puducherry-6.** The quotation without EMD will be summarily rejected.

If the opening day of the quotation happens to be a public holiday the same will be received and opened on the next working day at the same time.

The work should be carried out as per the CPWD Manual & Specifications and instruction of Engineer in-charge, and completed **within Two Months**, failing which MGPGIDS reserves the right to recover compensation for delay at the rate of 1% of the quoted amount pending subject to a maximum of 10% of the quoted amount.

The undersigned reserves the right to accept or reject whole or any part of the quotation and the quotationer shall be bound to perform the same at the rate quoted by him.

Note:

This quotation notice & Schedule is available in this Institution Website <https://mgpgi.py.gov.in> which may be downloaded.


ASSISTANT ENGINEER

Copy to the Programmer, MGPGIDS for uploading on MGPGIDS Website please.
(The previous schedule of items may be



**MAHATMA GANDHI
POSTGRADUATE INSTITUTE OF DENTAL SCIENCES
GOVT. OF PUDUCHERRY INSTN.
PONDICHERRY - 605 006**

Phone : 0413-2279601 - 2279606
E-mails : mgdch.pon@nic.in,
mgpgids@gmail.com
Websites: <https://mgpgi.py.gov.in>
<https://mgpgi.edu.in>

SCHEDULE

Name of Work: - Repair works inside the toilets of Medical and Surgery ward in MGPGI, Gorimedu, Puducherry.

Mahathma Gandhi post Graduate Institute of Dental

Sciences Engineering cell, Gorimedu, Puducherry.

S.No	Description	Qty.	Rate (Word & figre)	Unit	Amount in Rs
1	<u>Code No.: 15.23.1:-</u> Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead - for thickness of tiles 10mm to 25mm.	38.00		Sqm	
2	<u>Code No.: 11.40.1L:-</u> Providing and laying rectified ceramic rustic / matt finish floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer) of 1st quality conforming to IS:15622 of approved make (Somany / Nitco) in all colours , shades, except white, ivory, grey, fume red brown, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement and matching pigments etc., complete.	38.00		Sqm	
3	<u>Code No.: 11.43:-</u> Fixing glazed /ceramic / Vitrified floor tiles with cement based high polymer modified quick - set tile adhesive (water based) conforming to IS:15477, in average 3 mm thickness - (Using 5 kg adhesive	38.00		Sqm	
4	<u>Code No.: 16.100:-</u> Acid cleaning for the existing Mosaic floors , glazed tiles work and removing the stains and decays to give a glassy look etc complte (The Acid used shall be 32% concentrated hydrochloric acid after taking on the precautionary measures).	138.52		Sqm	
5	<u>Code No.:15.12.1:-</u> Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead - of area 3 sqm and below.	9.00		each	Cntd.2/3..
MGPGI-F288-Page 2/3..					

6	<u>Code No. 14.1.1:</u> Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq.metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead - with cement mortar 1:4 (1 cement : 4fine sand).	18.00		Sqm	
7	<u>Code No.:9.119:</u> Providing and fixing factory made P.V.C.door frame of size 50x 47 mm with a wall thickness of 5mm , made out of extruded 5 mm rigid PVC foam sheet, mitred at corners and joined with 2 nos , of 150mm long brackets of 15 x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19 x19 mm M.S.square tube of 19 gauge , EPDM rubber gasket weather seal to be provided through out the frame . The door frame to be fixed to the wall using M.S.screws of 65 / 100 mm size, complete as per manufacturer's specification.	37.00		Metre	
8	<u>Code No.: 9.120.1:</u> Providing and fixing factory made panel PVC) door shutter consisting of frame made out of M.S.tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15 x15 mm for top & bottom rails. M.S.frame shall have a coat of steel primers of approved make and manufacture . M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 m m shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top , bottom and lock rails shall be provided both side of the panel. 10mm (5 mm x 2) thick , 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail , panelling of 5 mm thick both.	16.00		Sqm	
9	<u>Code No.:9.95.8:-</u> Providing and fixing ISI marked aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws	30.00		each	
10	<u>Code No.:9.97.5:</u> Providing and fixing aluminium tower bolts, ISI marked , anodised (anodic coating not less than grade AC 10 as per IS :1868) , transparent or dyed to required colour or shade , with necessary screws etc.	18.00		each	
11	<u>Code No.:9.100.3:-</u> Providing and fixing aluminium handles , ISI marked , anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade,with necessary screws etc, complete - 75 mm	18.00		each	Cntd.3/3..

	MGPGI-F288-Page 3/3..				
12	<u>Code No.: 14.46:-</u> Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc complete.	174.00		Sqm	
13	<u>Code No.: 13.43.1:-</u> Applying one coat of water thinnable cement primer of approved brand and manufacturer on wall surface - water thinnable cement	174.00		Sqm	
14	<u>Code No.: 14.66.1:-</u> Finishing walls with acrylic smooth (sqm 71.39) exterior paint of required shade - old work (two or more coats applied @1.67 ltr / 10 sqm) on existing cement paint surface.	174.00		Sqm	
Total Amount in Rs					

.Sd.
ASSISTANT ENGINEER
MGPGI